



Generation Interconnections

The size and location of new or expanded power plants can have significant impacts on the transmission system. These impacts can range from very positive (adding voltage support in a weak area of the system) to very negative (aggravating loading problems and/or causing generator instability). Information on the status, as of July 1, 2010, of ATC's portion of the Midwest Independent System Operator generation interconnection queue is provided in this section. There continues to be significant activity in ATC's portion of this queue, ranging from newly proposed generation projects to cancellation of previously proposed generation projects.

There are two key aspects in determining the total impacts a proposed new generator may have on the transmission system:

- Impacts of interconnecting the new generator to the transmission system and
- Impacts of using the transmission system to deliver power from the new generator.

Per the Midwest ISO Revised Attachment X process, a generator interconnection study is usually performed in three stages: Interconnection Feasibility Study (Application Review Phase), Interconnection System Impact Study (System Planning and Analysis and/or Definitive Planning Phase), and an Interconnection Facilities Study (Definitive Planning Phase)

The *Interconnection Feasibility Study* includes a determination of thermal overload or voltage level impacts created by the new generator. This study process is now performed by MISO approximately five to six times per calendar year and provides a qualitative screen of the affected facilities, indicating if there is ample capacity on the system to support the new interconnection. Depending on the results of the study, the request may either enter into the Definitive Planning Phase (DPP), System Planning and Analysis Phase (SPA) or Customer Not Ready Phase of the Interconnection System Impact study.

The *Interconnection System Impact Study* includes a determination of whether the proposed generator and other nearby generators will remain connected to the system under various disturbance situations, such as line trips and equipment failures and includes a fault duty analysis to determine whether existing system equipment can accommodate the increased short circuit fault duty caused by the new generator. Finally, the Interconnection System Impact Study will identify solutions for any thermal, stability or fault duty deficiencies.

Delivery impacts are assessed during the DPP portion of the interconnection study process using the Midwest ISO deliverability methodology, which determines whether a new generator is deliverable to the Midwest ISO Day 2 market and to what percent if not wholly deliverable. Whatever portion of the new generator that is deliverable may then be used as



10-Year Assessment

An annual report summarizing proposed additions and expansions to the transmission system to ensure electric system reliability.

2010

September 2010 10-Year Assessment
www.atc10yearplan.com

a Network Resource by Network Customers through the Midwest ISO's Module E Resource Adequacy procedures.

The facility study is conducted in the DPP process phase to specify and estimate the time and cost of the equipment, engineering, procurement and construction of the system upgrades identified in the earlier interconnection studies.

The results of the interconnection studies are needed to develop a comprehensive picture of the transmission facilities that will be required for a proposed generator. This is why we included in our assessment models those proposed generators for which interconnection studies have been completed.

The first portion of this section provides the status of the generation queue within our service territory. The second portion of this section describes the transmission system additions associated with various proposed generation projects for which final interconnection studies have been completed. The third portion of this section describes some of the implications associated with interconnecting generation at various locations within our service territory.

ATC Generation Queue

Since ATC's inception, seventeen new generators have gone into service and two up rates to existing generators have been completed, totaling 4,943 MW. These generators are shown in [Table PR-26](#).

[Table PR-27](#) lists the proposed generators in the generation queue for our service territory as of July 1, 2010. This table lists each proposed generation project and summarizes them by planning zone and MW amount. These proposed projects also are shown by approximate location in [Figure PR-9](#). As shown, the total capacity of proposed generators in the queue is 3533.1 MW. Of that proposed capacity, 18 percent reflects new coal units; wind units reflect 75 percent; biomass reflect 2 percent; nuclear up-rates reflect 3 percent and the remaining 2 percent is comprised of simple cycle (natural gas) turbines (see [Figure PR-10](#)). Of this generation, 18 percent in Zone 5, 26 percent in Zone 4, 44 percent is proposed in Zone 3, 9 percent in Zone 2, and 3 percent in Zone 1. [Table PR-29](#) lists the required network upgrades associated with the generators shown in [Table PR-27](#) with a signed Interconnection Agreement.

The developer's projected in-service date listed in [Table PR-27](#) is the last official commercial operation in-service date provided by the developer for that request. Under the Midwest ISO's former Attachment X procedures, a developer may suspend their Interconnection Agreement which may delay the project and is not required to update their official in-service date as part of this suspension.



The following requests have been suspended:

- G546 – 100 MW wind farm, Line 6541 in Walworth County, Wisconsin
- G590 – 98 MW wind farm, Line 971K91 in Calumet County, Wisconsin

Generation interconnection requests previously in the generation queue, which have been cancelled or removed from the queue since July 1, 2009 (because the developer withdrew the request or missed contractual milestones), are summarized in Table PR-28.

Link to publicly posted generation queue:

http://oasis.midwestiso.org/documents/ATC/Cluster_8_Queue.html

Transmission associated with proposed generation interconnections

Prior to the start of the MISO Day 2 Market, transmission service for new generators was handled separately through an OASIS transmission service request(s). For generators listed below that had studies completed prior to Day 2 start-up, system reinforcements were identified through both generator interconnection and transmission service studies.

Implications of generation development

Availability of fuel, water and transmission interconnections are among the key aspects to be considered when sighting generation.

From a transmission perspective, the ability of the transmission system to accommodate new generation is a function of stability, power flow and short circuit analyses. For certain generation technologies, harmonics and voltage fluctuations may need to be considered as well. In most instances, new generation will require certain transmission system reinforcements to interconnect and deliver the generation output. In a few specific instances, new generation can be beneficial to the transmission system, perhaps even deferring or eliminating the need for transmission reinforcements that would be necessary absent the new generation. The ability of generation to defer or eliminate the need for transmission reinforcements also can be a function of the generation location, number of generators and/or expected generator capacity factor.

In this section, a general zone-by-zone evaluation of the likelihood of needing or deferring transmission reinforcements for various generator locations is provided. The purpose of these evaluations is to provide a cursory indication to the generation market of the likely magnitude of the impact and the transmission reinforcements that would likely be needed by general location.

Zone 1

Within Zone 1, generation has been proposed in various locations, but most of the proposals have involved generation located in the vicinity of the 345-kV infrastructure.



10-Year Assessment

An annual report summarizing proposed additions and expansions to the transmission system to ensure electric system reliability.

2010

September 2010 10-Year Assessment
www.atc10yearplan.com

Based on studies that we have conducted for proposed generation interconnections and transmission service from this area to date, some transmission reinforcements are likely to be required for any significant (>100 MW) generation development. The extent and nature of the reinforcements largely would be a function of where the power from the generation is to be delivered.

The reliability of the northern portion of Zone 1, the Rhinelander Loop, has been significantly improved with the completion of the new Cranberry to Conover 115-kV line and the Conover to Plains 138-kV conversion. While no new generator requests have been studied for this area, the addition of the Rhinelander Loop improvement projects may be able to support small-sized (up to 50 MW, depending on location) generation development, provided generator stability can be maintained, and provided it can be located in the northern portion of the Loop. Whether this generation would be cost-effective as a transmission-deferral mechanism would depend on a number of factors. The need for additional stability and thermal reinforcements in and outside of the Loop would be a function of where the new generation is sited and where the power is to be delivered. These improvements will be required to ensure that NERC reliability standards are continuously being met and that the security of the Rhinelander loop is not compromised.

The transmission infrastructure in the central portion of Zone 1 includes three new 345-kV lines which make up the GCMW corridor (Gardner Park – Highway 22, Morgan – Highway 22, and Highway 22 – Werner West). These additional lines significantly strengthen the Weston area, bringing much needed support to the area for both stability and thermal considerations for the new Weston 4 generation facility. A new generating facility was studied interconnecting 50 MW of biomass generation to the 115-kV transmission system located near the Weston substation. This study proved that properly sighted generation of 50 MW or less can be accommodated to the transmission system in the area with minimal network upgrades. While the evaluation of new generation in this area is limited to this one study, it is possible that the GCMW corridor has the potential to support additional small to medium size generation development depending on actual physical location of the facility.

The infrastructure in the southern portion of Zone 1 consists of five 138-kV lines and several 69-kV lines. Only smaller generation projects (typically <25 MW) could be accommodated with minimal transmission reinforcements. The existing infrastructure in this portion of Zone 1 is not suitable for significant generation development.



Zone 1 completed generation studies:

Request	Size	Type	County, State	Status
G144	550 MW	Coal	Marathon County, WI	In-Service
G522	550 MW	Coal	Portage County, WI	Out of Queue
G523	550 MW	Coal	Marathon County, WI	Out of Queue
G588	55/60 MW	Combustion Turbine	Wood County, WI	In-Queue
J040	50 MW	Biomass	Marathon County, WI	In-Queue

Zone 2

We have completed studies of seven generation interconnection requests for the Zone 2 area. Even though the first six requests are no longer active in the queue, they have helped us build a base of knowledge similar to what we have in other zones relating to likely generation interconnection impacts.

ATC is beginning to see substantial interest in siting wind turbine generators in the Upper Peninsula of Michigan. ATC has completed studying four wind farms located in Marquette, Houghton and Delta counties totaling 379 MW. One of the major challenges wind farms proposed for the Upper Peninsula will face is the limited transmission infrastructure to interconnect and deliver the energy produced by these power plants. Since the Upper Peninsula transmission grid was primarily designed to serve local load, substantial transmission upgrades area required to accommodate these proposed plants. The completion of the Northern Umbrella Plan, however, will result in a much more robust 138-kV network at Plains Substation that could accommodate a reasonable amount of generation in the future at or near Plains.

It is likely that given the scarcity of 138-kV infrastructure in the Upper Peninsula there are virtually no other locations in Zone 2 that are ideal candidates for significant generation development. Generation studies have indicated substantial re-enforcements are required to site large amounts of generation throughout the Upper Peninsula.

There are areas in Zone 2, such as on the western end of the Upper Peninsula, which are or will be in need of transmission reinforcements where smaller generation projects could be beneficial in terms of deferring transmission expenditures. The allowable capacity of such generation would depend on the location. However, other potential impacts (stability, fault duties) would need to be evaluated on a location-by-location basis.



Zone 2 completed generation studies:

Request	Size	Type	County, State	Status
G567-568	165 or 300 MW	Coal	Delta County, MI	Out of Queue
G583	19 MW	Biomass	Ontonagon County, MI	Out of Queue
G750	201 MW	Wind	Marquette County, MI	Out of Queue
G799	120 MW	Wind	Houghton County, MI	Out of Queue
G937	29 MW	Wind	Delta County	Out of Queue
J039	50 MW	Biomass	Delta County	Out of Queue
J060	29 MW	Wind	Delta County	In Queue

Zone 3

In Zone 3, generation has been proposed in various locations, but over half have been in the southern-most counties in Zone 3. Generation could be beneficial in a few areas depending on the capacity of such generation and the exact location.

We are projecting that the Dane County electric system could become subject to thermal overloads, low voltages or voltage collapse, significant load shed risk, and restrictions on power imports into the county as early as 2011. ATC will be extending the 345-kV network to the west side of the Madison metropolitan area and introducing additional 138-kV reinforcements and reactive support within the city to resolve these issues over the long term.

Even with the on-going reinforcement plans, Sauk County is projected to need additional transmission reinforcements in the future to ensure reliable operation. Smaller-scale generation (< 100 MW) in certain locations could be beneficial to improving the voltage profile in the area and potentially deferring transmission reinforcements. Stability analysis would need to be conducted to ensure stable operation of such generation.

Similarly, the southeast portion of Zone 3 is heavily loaded and will require transmission reinforcements in the future to ensure reliable operation. Small-scale generation in certain locations could be beneficial to changing power flow patterns and improving the voltage profile in the area. Generation studies completed in the southwest corner of the state have demonstrated that sighting large amounts of generation in rural areas may require substantial upgrades to the transmission system to ensure reliable operation.



Zone 3 completed generation studies:

Request	Size	Type	County, State	Status
G281	130 MW	Wind	Green County, WI	Out of Queue
G282	99 MW	Wind	Lafayette County, WI	In Queue
G338	54 MW	Wind	Dodge County, WI	In Service
G366	80 MW	Wind	Columbia County, WI	Out of Queue
G371	100 MW	Wind	Columbia County, WI	Out of Queue
G483	50 MW	Wind	Green County, WI	Out of Queue
G506	100 MW	Wind	Monroe County, WI	Out of Queue
G527	280 MW	Coal	Grant County, WI	Out of Queue
G528	550 MW	Coal	Columbia County, WI	Out of Queue
G546	100 MW	Wind	Walworth County, WI	In Queue
G550	24 MW	Simple cycle	Jefferson County, WI	In Service
G553	280 MW	Coal	Columbia County, WI	Out of Queue
G706	99 MW	Wind	Columbia County, WI	In Queue
G724	99 MW	Wind	Dane County, WI	Out of Queue
G747	99 MW	Wind	Rock County, WI	Out of Queue
G749	50 MW	Wind	Lafayette County, WI	In Queue
G793	100 MW	Wind	Rock County, WI	Out of Queue
G901	600 MW	Wind	Winnebago County, IL	Out of Queue
G902	600 MW	Wind	Winnebago County, IL	Out of Queue
G953	49.5 MW	Wind	Grant County, WI	Out of Queue
G954	49.5 MW	Wind	Grant County, WI	Out of Queue
H012	150 MW	Wind	Columbia County, WI	In Queue
H024	48 MW	Wind	Columbia County, WI	Out of Queue
J084	50 MW	Wind	Grant County, WI	In Queue

Zone 4

Generation has been proposed in various locations in Zone 4. Generation could be beneficial in a few areas depending on the capacity of such generation and exact location. One area where generation could defer the need for transmission reinforcements is in Door County, provided such generation is small-scale (< 50 MW) and appropriately located. Currently, the northern portion of the county is served radially, and electric service is subject to interruption for the loss of the single 69-kV line serving the area. The voltage profile in Door County is projected to precipitate the need for reinforcements in the future. Small-scale generation potentially could defer certain of these reinforcements.

One area in Zone 4 that cannot easily accommodate additional generation without significant transmission reinforcements is the area around the Point Beach and Kewaunee nuclear plants. In this area, existing transmission lines have little excess capacity and the



existing generation request have demonstrated that large scale transmission projects are a must for even modest increases in existing capacity. As the system evolves, stability margins at those plants may become a concern even with the transmission improvements. Additional generation wishing to site in the area will require extensive studies to ensure that system reliability will continue to be met for the existing generators in the area.

Zone 4 completed generation studies:

Request	Size	Type	County, State	Status
G240	54 MW	Steam	Manitowoc County, WI	In Service
G353-4	145 MW	Wind	Fond du Lac County, WI	In Service
G368	129 MW	Wind	Fond du Lac County, WI	In Service
G376	160 MW	Wind	Green County, WI	In Queue
G384	99 MW	Wind	Manitowoc County, WI	Out of Queue
G410	99 MW	Wind	Kewaunee County, WI	Out of Queue
G421	50 MW	Wind	Brown County, WI	Out of Queue
G427	98 MW	Wind	Fond du Lac County, WI	In Queue
G486	10.5 MW	Wind	Manitowoc County, WI	Out of Queue
G507	68 MW	Wind	Fond du Lac County, WI	In Service
G524	550 MW	Coal	Brown County, WI	Out of Queue
G590	98 MW	Wind	Calumet County, WI	In Queue
G611	99 MW	Wind	Calumet County, WI	In Queue
G773	150 MW	Wind	Brown County, WI	In Queue
G833	53 MW	Nuclear	Manitowoc County, WI	In Queue
G834	53 MW	Nuclear	Manitowoc County, WI	In Queue
G927	1.5 MW	Wind	Calumet County, WI	In Queue
G987	400 MW	Wind	Brown County, WI	Out of Queue

Zone 5

Two major generation additions have been completed for Zone 5. The first addition is at Port Washington Power Plant, which was declared for commercial operation on June of 2008. In order to accommodate the two blocks of generation at Port Washington, the two Port Washington–Rangeline 138-kV lines and the three Port Washington–Saukville 138-kV lines were rebuilt in 2005 and the Saukville–Pleasant Valley–Arthur Road–St. Lawrence 138-kV line was rebuilt in 2007 at a cost of approximately \$10 million.

The other site for new generation is the Oak Creek Power Plant. The PSCW has approved two units at the Oak Creek Power Plant, with the first unit having gone into service December 2009 and the second unit due to go in-service early Fall 2010.



10-Year Assessment

An annual report summarizing proposed additions and expansions to the transmission system to ensure electric system reliability.

2010

September 2010 10-Year Assessment
www.atc10yearplan.com

Studies of other proposed generation projects that are no longer in the generation queue indicate that additional generation in certain areas of Zone 5 would pose stability problems. In particular, larger-scale generation interconnecting to the 345-kV network could pose stability issues.

Smaller-scale generation in certain locations in Washington and Waukesha counties potentially could be accommodated without the need for transmission reinforcements if located appropriately.

Zone 5 completed generation studies:

Request	Size	Type	County, State	Status
G051	1300 MW	Coal/steam	Milwaukee County, Wisconsin	First block In Service
G093/G510	1200 MW	Combined cycle	Ozaukee County, Wisconsin	In Service