

Table PR-11
Transmission System Additions for 2015

System additions	System need year	Projected In-service year	Planning zone	Need category	Planned, Proposed or Provisional	Cost Estimate - Refer to Funding Project and Sum of Total (2006-2015) in Financial Table
Install a second 138/69-kV transformer at Wautoma Substation	2015	2015	1	reliability	Provisional	F0817
Install 2-16.3 MVAR capacitor bank at Aviation Substation	2015	2015	4	reliability	Provisional	F1923
Install 28.8 MVAR capacitor bank at Butternut 138-kV Substation	2015	2015	4	reliability	Provisional	F1403
Replace two existing 138/69-kV transformers at Sunset Point with 100 MVA transformers	2015	2015	4	reliability	Provisional	F2080
Reconductor Pulliam-Danz 69-kV line	2015	2015	4	reliability	Provisional	F1622
Reconductor Danz-Henry Street 69-kV line	2015	2015	4	reliability	Provisional	F1623
Reconductor Pulliam-Van Buren 69-kV line	2015	2015	4	reliability	Provisional	F1624

Defined in Previous 10-Year Assessment
Revised in scope from Previous 10-Year Assessment
New to this 10-Year Assessment