

Table PR-9
Transmission System Additions for 2015

System Additions	System Need Year	Projected In-Service Year	Planning Zone	Need Category	Planned, Proposed or Provisional	Cost Estimate - Refer to Funding Project and Sum of Total (2008-2017) in Financial Table
Construct a Lake Delton-Birchwood 138-kV line	2015	2015	3	reliability	Provisional	F1638
Replace the existing 46 MVA Hillman 138/69-kV transformer with a 100 MVA transformer	2015	2015	3	reliability	Provisional	F0339
Rebuild part of the Y-8 Dane-Dam Heights 69-kV line	2015	2015	3	reliability	Provisional	F1602
Uprate Columbia 345/138-kV transformer T-22 to 527 MVA	2015	2015	3	reliability	Provisional	F2135
Uprate Y159 Brick Church-Walworth 69-kV line to 115 MVA	2015	2015	3	reliability	Provisional	F2153
Install 2-16.3 MVAR capacitor bank at Mears Corners 138-kV Substation	2015	2015	4	reliability	Provisional	F1924
Install 2-16.3 MVAR capacitor bank at Rosiere 138-kV Substation	2015	2015	4	reliability	Provisional	F1925

Defined in Previous 10-Year Assessment
Revised in scope from Previous 10-Year Assessment
New to this 10-Year Assessment