

2024 10-Year Assessment Preliminary Study Design

Stakeholder and Customer Webcast

PRESENTED BY:

System Planning

November 13, 2023

- ATC Proprietary -

atcllc.com


Purpose

- Summarize ATC's project development processes
- Solicit input for the 2024 Assessment Study Design
- Solicit input on any new Public Policy Requirements


ATC's project development processes

- Local Transmission Planning
 - Asset Renewal
 - Interconnections
 - Network
 - ◆ Planning Reliability Criteria
 - ◆ Sectionalizing Guidelines
 - Economic Benefits
- Consider Other Solutions (Non-Transmission Alternatives)
- Regional Planning
- Public Policy Requirements


Timeline



ATC project identification process



ATC project status definitions



Asset renewal program objectives

- Safety – public and worker
- Minimize total life cycle cost [Net Present Value of Revenue Requirements (NPV RR) from customer cost/rate perspective]
- Compliance
- Manage risk
- Reliable performance – maintain or improvement
- Environmental performance improvements
- Coordination with Stakeholders

Replacement is based on...

- Safety – public and worker
- Condition – tests, maintenance costs/risks
- Obsolescence – part availability, factory support, craft labor expertise with this specific equipment, available spares
- Utilization – application, system changes
- Criticality – consequence of failure, outage impacts
- Costs – maintenance and replacement
- Environmental – PCB contamination, oil volumes and containment, proximity to waterways, SF6 gas leaks, lead, mercury, environmental compliance/risks
- Compliance – NERC, CIP, EPA, State DNR
- Other Considerations – test frequency, on-line monitoring, test information available, fleet size, common fleet issues, maintenance history, failure mode, industry experience

Asset renewal considerations

- Is the asset still needed?
 - Assess area needs
 - Obtain cross-functional and distribution provider input
 - Consider removal of lines/equipment
 - Consider system reconfiguration
 - Other alternatives
- What ratings and performance are needed?

Asset Renewal T-line Project Example

- Portage – Dam Heights 69kV Rebuild (Y-16)
 - Project Background
 - ◆ Approximately 25 of miles of rebuild
 - Past Needs
 - ◆ Condition and Performance Issues
 - ◆ Replace 1910's vintage lattice structures
 - ◆ Outages: One of the most frequently outaged ATC lines
 - ✓ On average about 4 outages per year
 - ✓ Updated to avian friendly design
 - ✓ Improved lightning performance
 - Current status
 - ◆ Project went in-service Fall of 2017
 - ◆ Improvement in performance: One momentary outage in 2021 due to lightning above design (69kV – 45kA design, actual strike 192kA)



Lancaster Power Transformer – Life Cycle

- Allis Chalmers Power Transformer built in 1954
- Life Extension – 2015
 - High Voltage Bushings
 - Load Tap Changer bypass
 - Oil Seal Gaskets
- Planned Retirement 2025 after LDC distribution buildout



Interconnections

- G-T
 - MISO Attachment X and Y Processes
- D-T
 - Collaborate with distribution providers through Load Interconnection Request Form (LIRF) and BVP process
- T-T
 - Collaborate with other Transmission Owners

Network planning objectives

- Compliance with North American Electric Reliability Corporation (NERC) regional and local criteria
- Best Value Planning (BVP) process
- Customer involvement
- Address Public Policy requirements
- Maintain or improve the adequacy and reliability of the electric transmission system

Planning Criteria and Assessment Practices

- NERC Standards, particularly [TPL-001, Version 5](#)
- ATC Planning Criteria
 - [Consists of criteria and assessment practices](#)
 - <http://www.atc10yearplan.com> (About tab)
 - Current versions: Planning Criteria v22.2 & Planning Assessment Practices v22.2
 - Planning Criteria v22.2
 - ◆ v22.2 (March 2023)
 - ✓ IBR Model Verification Process Update to Section 4
 - Planning Assessment Practices v22.2
 - ◆ v22.2 (March 2023)
 - ✓ Included a generator outlet emergency rating requirement in Section 13.6.1
 - ✓ Included a requirement of interconnection customers using ATC Area Generator Material Modification Study Review Template when submitting a generator material modification study in Section 13.8.

2023 studies and assumptions

- Preliminary 2023 Load Forecast Confirmation and MTEP24 Support Studies
- Modeling Assumptions
 - Model Years
 - Load
 - Generation
 - No Load Loss Allowed Contingency Analysis
- Additional Studies

Preliminary load forecast and MTEP24 support studies

- Initial screening (reduced generator reactive capability)
 - Summer peak (5 and 10 year models)
 - 2023 load forecast
 - 2023 TYA outside world (2022 MMWG cases)
- To confirm 2023 Load Forecast and support MTEP24 database development
 - No load loss allowed contingencies
 - Completed August 2023

2024 TYA model years

- 2024 (As-planned)
 - 2025
 - 2029
 - 2034
-
- All models will likely be completed by the Spring of 2024

2023 Load Forecast- Historical


- Requested September 29, 2023
 - ATC's 2023 summer peak hour
 - ATC's 2022-2023 winter peak hour
 - Light load
 - Shoulder load
- Requested by November 1, 2023.
- Compile, review, and add to the existing load databases

2023 Expected forecast for TYA 2023

- Requested LDC forecasts in February 2023
 - 11 years per D-T IA
 - Consistent with resource planning forecast
 - Expected (50/50 probability)
- Received in April 2023
- ATC compares forecasts to previous forecasts and historic data
 - Notable differences are confirmed with the LDCs and revised if needed
 - Finalized copy of forecast provided to LDCs in August 2023
 - Forecasts incorporated into the 2024 TYA to plan the system

ATC 2023 Load Forecast Comparison

Comparisons of ATC TYA Forecasts



Annual growth rates
(2023-2033 for all)

2020 Forecast: 0.35%
 2021 Forecast: 0.25%
 2022 Forecast: 0.15%
 2023 Forecast: 0.11%

ATC Load Forecast Growth by Zone 2023-2033 Annual Growth Rates

Zone	Forecast Year			
	2023	2022	2021	2020
Zone 1	0.1%	0.2%	0.3%	0.4%
Zone 2	0.7%	0.4%	0.2%	0.3%
Zone 3	0.2%	0.3%	0.3%	0.5%
Zone 4	0.0%	0.0%	0.1%	0.2%
Zone 5*	0.1%	0.1%	0.2%	0.3%
ATC Total	0.11%	0.15%	0.21%	0.32%

*Zone 5 influenced by Racine County growth.

Load forecast trends, (*Continued*)

Model	ATC Load (MW)		
	2021 Assessment	2022 Assessment	2023 Assessment
Year 1 Summer Peak	12,700	12,800	12900
Year 5 Summer Peak	+300	+100	+100
Year 10 Summer Peak	+400	+300	+200
Year 5 Shoulder	9,300	9,100	9200
Year 10 Shoulder	+200	+100	+100

Generation modeling

- Existing generator data
 - Annual updates requested from Generator Owners (GOs) in Q3
- Generation additions
 - Only add generators with signed interconnection agreements (IAs)
 - Additions modeled at MISO Facility study location
- Generation retirements
 - Generators with a completed MISO Attachment Y are modeled as retired, unless there is a System Support Resource (SSR) agreement
- Under intact system and outage conditions
 - Generators are limited to:
 - ◆ 90% of maximum reactive power output and
 - ◆ 90% of maximum reactive power consumption

Generation dispatch

- Local Balancing Area (LBA) merit order dispatch:
 - Used in Assessment's summer peak and shoulder models.
 - Provided by LBAs
- ATC-wide merit order dispatch:
 - Used in minimum load models
 - ATC-wide merit order dispatch determined using PROMOD
- Generators without scheduled transactions:
 - If they have signed IAs, generator included in the host LBA.

No load loss allowed contingency analysis

- Peak
 - 1, 5, and 10 year out models
- Shoulder (firm)
 - 5 and 10 year out models
 - 70% load except for Zone 2 (90% load) and northern Zone 4 (80% load)
 - Shoulder rating methodology
- Minimum load
 - 1 and 5 year out model
 - 40% load, may be adjusted based on analysis of historical loads

Additional network planning studies

- Load Loss Allowed
- Existing Generator Stability Reviews
- Annual Fault Study
- Sensitivity Studies

Long Range Transmission Plan (LRTP)

- MISO led initiative, under the Reliability Imperative
 - Transmission solutions to provide reliable and economic energy delivery for a reliable energy future
- 4 Tranches planned
 - Tranche 1
 - ◆ Approved by the MISO Board retroactively to MTEP21 in 2022
 - ◆ Portfolio of 18 projects for \$10.3 B
 - ◆ ATC ownership share in 3 projects
 - Tranche 2
 - ◆ Under development and study, ATC actively participating
- Latest information available at [MISO's LRTP Page](#)



Projects Flow from the TYA to MTEP

- Projects developed in the 2023 TYA process will be included in the MTEP24 approval process
 - A list of those projects can be found in the [2023 TYA Project List](#)
- Projects that may develop subsequent to the 2023 TYA process would be included on the project list and will be submitted into MTEP24
- [MISO Active Project List](#)

MTEP24 – Summary (as of 10/27/23)

- Appendix A Projects
 - Count: 15
 - Est Cost: \$504,400,000
- Appendix B Project
 - Count: 34
 - Est Cost: \$1,051,200,000
- Remaining Appendix B Projects
 - Count: 17
 - Est Cost: \$484,600,000

MTEP24 Appendix A
Project Breakdown

Project Category	Count
Baseline Reliability Project	0
Generator Interconnection Project	0
Other – Local Reliability	4
Other – Age and Condition	3
Other – Load Growth	5
Other – Other Local Need	3
Total	15

Non-Transmission Alternatives (NTAs)

- ATC and MISO work together in the TYA and MTEP processes to provide Stakeholders an opportunity to provide NTA Feedback on Projects
- MISO will post a list of NTA eligible projects as part of their Subregional Planning Meeting (SPM) #1, in January of 2024.
 - MISO will accept stakeholder project alternatives through May 31, 2024.
 - Best candidates for NTA consideration are MTEP Appendix B and Target Appendix B projects.
 - Stakeholders should submit alternatives to MISO's MTEP SPM contact, who is [Greg Plauck](#).

Regional planning

- MTEP
- MISO's Coordinated Seasonal Assessments
- Reliability First's (RF's) Seasonal Assessments

Public policy requirements

- Follow MISO Tariff (Attachment FF) Processes
- Previously identified requirements
 - State Renewable Portfolio Standards (RPSs)
 - EPA regulations
 - State mandates and goals for energy efficiency (EE) and demand side management (DSM) programs
- We are asking for any feedback on whether there are additional public policy requirements we need to be made aware of.

Schedule

- Expected Load Forecast – Review complete August 2023
- Preliminary MTEP23 Support Study – Done
- Post 2023 TYA Preliminary Study Design Presentation – Done
- Stakeholder Preliminary Study Design Meeting – November 13, 2023
- Stakeholder Study Design Comments Due – November 30, 2023
- Study Design Completion – December 2023
- Preliminary Needs Meeting – March 2024
- Preliminary Solutions Meeting – May 2024
- Document and Publish – November 2024

Thank you for participating

To provide solicited comments or for more information, please contact:

Ted Weber (tweber2@atcllc.com)

by November 30, 2023

Q&A

